



KEYNOTES

- ① Concrete Substrate
- ② Wall
- ③ Cement Backerboard (Thickness as needed)
- ④ Schluter Strip (By Others)
- ⑤ Epoxy Radius Cove
- ⑥ Epoxy Flooring System
- ⑦ Tile (By Others)

- Concrete must be a minimum 2,500 PSI.
- Concrete must be cured for a minimum 28 days.
- Concrete should be prepared to a profile equal to ICRI CSP 3-5.
- Refer to local building codes and standards.
- Refer to all Product and System Specifications for additional information.
- Epoxy Radius may vary depending on building code or facility requirements.

REV. 4/20/23 - TC

EPOXY COVE - COVE BASE (BUILT OUT WALL)

DIVISION 09 67 23
Resinous Flooring

SCALE : NTS



westcoat
SPECIALTY COATING SYSTEMS

4007 Lockridge Street • San Diego, CA • 92102
800.250.4519 • westcoat.com