



## KEYNOTES

- ① Concrete Substrate
- ② Wall
- ③ Epoxy Radius Cove
- ④ Epoxy Flooring System
- ⑤ FRP Edge Trim Molding
- ⑥ FRP

- Concrete must be a minimum 2,500 PSI.
- Concrete must be cured for a minimum 28 days.
- Concrete should be prepared to a profile equal to ICRI CSP 3-5.
- Refer to local building codes and standards.
- Refer to all Product and System Specifications for additional information.
- Epoxy Radius may vary depending on building code or facility requirements.

REV. 12/15/20 - TC

### EPOXY COVE - FRP WALL PANEL TERMINATION

DIVISION 09 67 23  
Resinous Flooring

SCALE : NTS



**westcoat**  
SPECIALTY COATING SYSTEMS

4007 Lockridge Street • San Diego, CA • 92102  
800.250.4519 • westcoat.com