Rolled Good Coverages:

Rolls of CA-60 Grout Tape for Tile Patterns (Based on 180' per roll)												
		Square Footage of Area										
		100	**150**	**200**	**300**	**400**	**500**	**600**	**700**	**800**	**900**	**1000**
Tile Pattern Size	**6"**	2	3	4	6	8	10	12	14	16	18	20
	12"	1	1.5	2	3	4	5	6	7	8	9	10
	18"	0.75	1.13	1.5	2.25	3	3.75	4.5	5.25	6	6.75	7.5
	24"	0.5	0.75	1	1.5	2	2.5	3	3.5	4	4.5	5
	30"	0.25	0.38	0.5	0.75	1	1.25	1.5	1.75	2	2.25	2.5

Note: Use only as a rough guide. Coverage will vary based on layout.
Please allow for waste and additional bordering.

Rolled Goods Coverage Chart (WP-40 Sheet Membrane or WP-47A Seam Tape for Plywood)											
		Square Footage of Deck									
		100	**200**	**300**	**400**	**500**	**600**	**700**	**800**	**900**	**1000**
# of Rolls Needed	**6" Seal Guard (75' per roll)**	0.44	0.89	1.33	1.78	2.22	2.67	3.11	3.56	4.00	4.44
	3" Seam Tape (100' per roll)	0.33	0.67	1.00	1.33	1.67	2.00	2.33	2.67	3.00	3.30

Note: Based on average amount of seams encountered, which is about 1/3 of the total square footage.
Example: 1000 sq. ft. job usually has 330 linear feet of seams (not including flashing).